

Project: Commercial Building Sample - 2 Story Building W basement - 6 Units / One Estimate
Model: Commercial Building
Take-Off: Per Plan

Quantity Take-Off By Category

The following is a categorized listing of the items that are included in the proposal.

01 - Single Items

9 20A White Surge Suppressor Duplex Receptacle

02 - Switch Assemblies

31 1-Pole White Toggle Switch, 15A

12 3-Way White Toggle Switch, 15A

2 4-Way White Toggle Switch, 15A

3 SP White Lutron Diva 600W Incandescent Dimmer

04 - Receptacle Assemblies

64 15A White Duplex Receptacle

16 15A White Duplex Receptacle - Surface Mounted

5 20A White Duplex Receptacle

1 240V 30A Receptacle

5 250V, 20A , 3 Phase Single Receptacle

1 250V, 50A , 3 Phase Single Receptacle

14 6' Plugmold With 15A Outlets Every 18" on Center

3 Bathroom 20A White GFI Duplex Receptacle

3 Floor Receptacle, 15A

Project: Commercial Building Sample - 2 Story Building W basement - 6 Units / One Estimate
Model: Commercial Building
Take-Off: Per Plan

Quantity Take-Off By Category

The following is a categorized listing of the items that are included in the proposal.

05 - Lighting Assemblies

5	Fixture Type A (Fixture FBO)
4	Fixture Type B (Fixture FBO)
18	Fixture Type C (Fixture FBO)
15	Fixture Type D (Fixture FBO)
24	Fixture Type E (Fixture FBO)
3	Fixture Type F (Fixture FBO)
2	Fixture Type G (Fixture FBO)
4	Fixture Type H (Fixture FBO)
27	Fixture Type I (Fixture FBO)
10	Fixture Type J (Fixture FBO)
27	Fixture Type L - Attached to Joist (Fixture FBO)
9	Fixture Type M (Fixture FBO)
10	Fixture Type N (Fixture FBO)
16	Fixture Type O (Fixture FBO)
2	Fixture Type P (Fixture FBO)
4	Fixture Type Q (Fixture FBO)
1	Fixture Type R (Fixture FBO)
5	WP Sign Outlets (Sign FBO)

08 - Exhaust Fan Assemblies

1	Exhaust Fan Circuit and Termination
---	-------------------------------------

11 - Mechanical Assemblies

2	20 Amp Sump Pump With Switch
1	30 Amp Water Heater - 40 Ft Ckt

Project: Commercial Building Sample - 2 Story Building W basement - 6 Units / One Estimate
Model: Commercial Building
Take-Off: Per Plan

Quantity Take-Off By Category

The following is a categorized listing of the items that are included in the proposal.

13 - Service Assemblies

- | | |
|---|----------------------------------------------|
| 1 | 125A 3P Load Center - Includes Feeders - 10' |
| 1 | 125A 3P Load Center - Includes Feeders - 20' |
| 1 | 125A 3P Load Center - Includes Feeders - 50' |
| 1 | 225A 3P Load Center - Includes Feeders - 30' |
| 1 | 225A 3P Load Center - Includes Feeders - 40' |
| 1 | 225A 3P Load Center - Includes Feeders - 70' |

21 - Disconnect and Safety Switch Assemblies

- | | |
|---|---------------------------------------------------|
| 7 | 60A 3P Fused Disconnect w/Connection |
| 4 | 60A 3P Raintite Fusible Safety w/Motor Connection |