

Project: Sample Remodel Job

Model: Room Addition

Take-Off: Scope of Work

## Quantity Take-Off By Category

---

The following is a categorized listing of the items that are included in the proposal.

### 01 - Single Items

---

- 1 1 Button Doorbell Chime Kit
- 1 Individual 120V Smoke / CO Detector Combo, 9V Battery Backup
- 1 Leviton Sureslide 600W Incandescent Dimmer - White

### 02 - Switch Assemblies

---

- 2 3-Way White Toggle Switch, 15A
- 4 1-Pole White Toggle Switch, 15A

### 04 - Receptacle Assemblies

---

- 1 Bathroom 20A White GFI Duplex Receptacle
- 2 1/2 Switched 15A White Duplex Receptacle
- 5 15A White Duplex Receptacle

### 05 - Lighting Assemblies

---

- 1 Ceiling Light, 10 Ft & Under
- 1 Wall Light, Interior
- 1 Flourescent Pull Chain

### 07 - Detector & Alarm Assemblies

---

- 1 Smoke Detector, 120V With Battery Back-Up
- 1 Combination Smoke / Carbon monoxide Detector

### 08 - Exhaust Fan Assemblies

---

- 1 Bath Exhaust Fan/Light, 50 CFM

### 10 - Low Voltage Assemblies

---

- 1 Single Cable Jack, 50 Feet
- 1 Flush Mount Phone Jack, Cat 5 - 50 Feet

Project: Sample Remodel Job

Model: Room Addition

Take-Off: Scope of Work

## Quantity Take-Off By Category

---

The following is a categorized listing of the items that are included in the proposal.

### 15 - Extra Labor for Remodeling/Cut-In Work and/or to Remove & Replace Existing Items

---

- |   |   |
|---|---|
| 1 | Switch Assembly Cut-In - 105 Additional Minutes             |
| 2 | Switch Assembly Cut-In - 120 Additional Minutes             |
| 1 | Receptacle Assembly Cut-In - 15 Additional Minutes          |
| 1 | Receptacle Assembly Cut-In - 90 Additional Minutes          |
| 1 | Lighting Assembly Cut-In - 75 Additional Minutes            |
| 1 | Detector & Alarm Assembly Cut-In - 90 Additional Minutes    |
| 2 | Branch Circuit Home Run Remodel - 120 Additional Minutes    |
| 1 | Switch Removal and Replacement Labor - 15 Minutes           |
| 1 | Detector & Alarm Removal and Replacement Labor - 15 Minutes |
| 1 | Low Voltage Removal and Replacement - 15 Additional Minutes |