

Project: Sample Remodel Job

Model: Room Addition

Takeoff: Scope of Work

Quantity Take-off by Room

The following is a room by room breakdown of what is included in this proposal.

1st Floor

2 Branch Circuit Home Run Remodel - 120 Additional Minutes

Dining Room

1 Leviton Sureslide 600W Incandescent Dimmer - White

1 Switch Removal and Replacement Labor - 15 Minutes

Family Room

1 1-Pole White Toggle Switch, 15A

1 1/2 Switched 15A White Duplex Receptacle

1 Switch Assembly Cut-In - 105 Additional Minutes

1 Receptacle Assembly Cut-In - 15 Additional Minutes

Guest Bedroom

1 1-Pole White Toggle Switch, 15A

1 1/2 Switched 15A White Duplex Receptacle

4 15A White Duplex Receptacle

1 Flourescent Pull Chain

1 Smoke Detector, 120V With Battery Back-Up

1 Single Cable Jack, 50 Feet

1 Flush Mount Phone Jack, Cat 5 - 50 Feet

Hall Bath

2 1-Pole White Toggle Switch, 15A

1 Bathroom 20A White GFI Duplex Receptacle

1 Wall Light, Interior

1 Bath Exhaust Fan/Light, 50 CFM

Project: Sample Remodel Job

Model: Room Addition

Takeoff: Scope of Work

Quantity Take-off by Room

The following is a room by room breakdown of what is included in this proposal.

Lower Hall

- | | |
|---|---|
| 1 | 1 Button Doorbell Chime Kit |
| 2 | 3-Way White Toggle Switch, 15A |
| 1 | 15A White Duplex Receptacle |
| 1 | Ceiling Light, 10 Ft & Under |
| 1 | Combination Smoke / Carbon monoxide Detector |
| 2 | Switch Assembly Cut-In - 120 Additional Minutes |
| 1 | Receptacle Assembly Cut-In - 90 Additional Minutes |
| 1 | Lighting Assembly Cut-In - 75 Additional Minutes |
| 1 | Detector & Alarm Assembly Cut-In - 90 Additional Minutes |
| 1 | Low Voltage Removal and Replacement - 15 Additional Minutes |

Upper Hall

- | | |
|---|--|
| 1 | Individual 120V Smoke / CO Detector Combo, 9V Battery Backup |
| 1 | Detector & Alarm Removal and Replacement Labor - 15 Minutes |