

## Quantity Take-Off

---

---

Project: Sample Service Project  
Estimate: Hot Tub, Landscape, Fan & Landscape Lighting  
Take-Off: Project Take-Off

The following lists the items that are included in this proposal.

### Misc. Expenses

---

1 Bucket Truck: 1/2 Day

### Guest Bedroom: Paddle Fan

---

- 1 Install 52" White Indoor Ceiling Fan (Outlet box not included)
- 1 Install Cathedral Center Mount Fan Box: Up to 50' 14/2 Romex Cable (Limited access: 1 Plate)
- 1 Install Decora Style Fan Light/Speed Control Switch (Switch box not included)
- 1 Install 1G Switch Box with Decorator Switch Wallplate: Up to 20' 14/2 Romex (Limited access: 1 Plate)

### Landscape Lighting

---

- 1 Troubleshoot & Replace (1) Non-Working 15A Tamperproof Weather-Resistant GFI Receptacle
- 1 Install 150W Black Transformer with Photo Cell and Timer to Existing GFCI Outlet
- 8 Install Lantern Path Light Landscape Fixture (Excludes trenching and wire)
- 1 Install up to 100' of 12/2 Low Voltage Cable

### Rear Exterior: Speakers

---

- 1 Install 14/2 Speaker Wire: Up to 50' (Limited access: 2 Plates)
- 1 Install 1G Low Voltage Mounting Bracket for Existing Construction
- 2 Install One Customer Supplied Speaker: Up to 50' 14/2 Speaker Wire (Limited access: 2 Plates)
- 1 Install or Replace Decora Style Volume Control Switch (Wire not included)

### Screen Room: Hot Tub

---

- 1 Bond Screen Room and Windows
- 1 Install Additional Ground Rod
- 1 Install Hot Tub GFCI Disconnect (Exposed conduit up to 6' from existing power source)
- 1 Install New 50A 120/240V Romex Circuit: Up to 50' (Limited access: 1 plate)